

2017 HMA OVERLAY

STREET NAME	SEGMENT	SCOPE OF WORK
W 32 ND AVE.	Morningside Dr. to Union St.	5,190sy 2" Full Width Planing 600tn 2" Overlay 2ea Man Hole Adjust 7ea Valve Adjust 1,800sf White Mod. Epoxy (Recess) 1,800sf White Mark (Temp) 30lf 24" White Mark (TAPE) 1ea Loop Detector (6'x40')
W 44 TH AVE.	Vance St to Harlan St Harlan St to Fenton St (East Bound Only)	27,000sy 2" Full Width Planing 3,165tn 2" Overlay 28ea Man Hole Adjust 21ea Valve Adjust 2ea Traffic Cameras 3,400sf Yellow Mod. Epoxy (Recess) 750sf White Mod. Epoxy (Recess) 3,400sf Yellow Mark (Temp) 750sf White Mark (Temp) 465lf 24" White Mark (Tape) 6ea Arrow (Straight) 6ea Arrow (Left) 6ea Arrow (Straight/Right)
DUDLEY ST.	Everett St to Everett St	5,415sy 1 1/2" Full Width Planing 475tn 1 1/2" Overlay 4ea Man Hole Adjust 3ea Valve Adjust 1ea Asphalt Speed Bump W/Arrows 100sf Yellow Mod. Epoxy (Recess)
EVERETT ST.	Dudley St to W 44 th Ave	4,450sy 1 1/2" Full Width Milling 400tn 1 1/2" Overlay 4ea Man Hole Adjust 3ea Valve Adjust 2ea Asphalt Speed Bump W/Arrows 200sf Yellow Mod. Epoxy (Recess)
I-70 North Frontage Road	Garrison St to Carr St	12,875sy 2" Full Width Planing 1,510tn 2" Overlay 4ea Man Hole Adjust 1ea Valve Adjust 1ea Man Hole Reconstruct 975sf White Mod Epoxy (Recess) 1,060sf Yellow Mod Epoxy (Recess) 975sf White Mark (Temp) 1,060sf Yellow Mark (Temp) 30lf White Mark 24" Tape (Recess)

2017 HMA OVERLAY

STREET NAME	SEGMENT	SCOPE OF WORK
I-70 North Frontage Road	Independence St to Garrison	4,315sy 2" Full Width Milling 505tn 2" Overlay 14ea Manhole Adjust 5ea Valve Adjust 1,025sf Yellow Mod Epoxy (Recess) 1,025sf Yellow Mark (Temp)
W 49 th AVE.	Independence St to Garrison	4,715sy 2" Full Width Planing 555tn 2" Overlay 4ea Man Hole Adjust 3ea Valve Adjust 0 2ea Arrow Left (15.5sf) (Tape/Recess) 240lf White Marking Tape 8" (Recess) 40lf White Marking Tape 24" (Recess) 220sf White Mod Epoxy (Recess) 1,050sf Yellow Mod Epoxy (Recess) 380sf White Pavement Marking (TEMP) 1,050sf Yellow Pavement Marking (TEMP)
OAK ST.	W 35 th PL to W 41 st Ave	5,000sy 1 1/2" Full Mill Planing 450tn 1 1/2" Overlay 12ea Man Hole Adjust 11ea Valve Adjust
	PATCHING	
Pierce St	32??	10 x 20
Quay St	28??	6 x 20
W 41 st Ave	@ Fenton St	10 x 30
W 32 ND Ave.	8080	5 x 15
Harlan @ 47 th Ave (I-70)		10x50
	STRIPING CITY WIDE	
W 38 TH AVE.	Kipling St to Dover St (E)	5,250sf Yellow Mod Epoxy (Recess) 160lf 8" White Mark Tape (Recess) 100lf 24" White Mark Tape (Recess) 34ea Arrow Left (15.5sf) (Recess)
W 38 TH AVE.	Dover St (E) to Wadsworth	2,750 sf Yellow Mod Epoxy (Recess)
W 50 TH AVE.	Kipling St to Miller St	1,300lf 4" White Mark Tape (Recess) 1,390lf 8" White Mark Tape (Recess) 380lf 24" White Mark Tape (Recess) 2ea Arrow Straight (15.5sf) (Recess) 4ea Arrow Right (15.5sf) (Recess) 6ea Arrow Left (15.5sf) (Recess) 3ea 8' " ONLY" Tape (Recess)
W 49 TH AVE.	Independence St to Kipling St	1,500sf Yellow Mod Epoxy (Recess) 200lf 8" White Mark Tape (Recess) 150lf 24" White Mark Tape (Recess)

2017 HMA OVERLAY

STREET NAME	SEGMNT	SCOPE OF WORK
	STRIPING CITY WIDE	
Youngfield St	W 32 nd Ave S to City Limit	6ea Arrow Left Tape (Recess) 1,650sf Yellow Mod Epoxy (Recess) 550sf White Mod Epoxy (Recess) 85lf 24" White Mark Tape (Recess)
W 26 TH Ave.	@ Wadsworth Blvd. (East) (West Bound)	250lf 8" White Mark Tape (Recess) 80lf 24" White Mark Tape (Recess)