



ITB-18-26
ADDENDUM #2 *4th*
REBID - 29th AVE REALIGNMENT PROJECT

Date: December 7, 2018
Bid Number: ITB-18-26
Bid Due Date: TUESDAY, DECEMBER 18, 2018 BY 1:00 PM OUR CLOCK

The following information is provided to all prospective bidders and is hereby made a part of the above bid documents. Bidders must acknowledge this five-page Addendum 2 with their bid. This addendum includes revised pages for Bid Schedule 4 and the Notice to Proceed.

CLARIFICATION, ADDITIONAL INFORMATION, AND CHANGES:

CLARIFICATIONS / QUESTIONS:

1. Is there a location for the nearest power source for the lighting and the Flashing beacons?

The power source for the lighting will need to be coordinated with Xcel. As noted in the City Special Provision Section 614, the flashing beacons are solar powered.

2. Are there details for what is needed for the Pay Item “Electrical Distribution System”?

The system is a lump sum item that is intended to cover all items necessary to meet the specifications to provide power to the lights.

3. Are there details or requirements for what is needed for the Pay Item “Meter Housing”?

The meter housing needs to meet Xcel standards.

4. The Pay Item “Electric Meter”, is that a cost for the actual Meter? This is normally something that the utility company provides. Please clarify what is needed for this pay item?

Xcel will provide the meter, this is the cost to pay Xcel for the meter.

5. What are the required dimensions for the Pay Item “Electric Box”? Are concrete collars required?

As noted in the CDOT Standard Specification Sub-Section 715.06, the pull boxes shall be a minimum of 16” x 12” x 6” deep.

6. Where is the installation location of the Pedestrian LED Signs?

As noted on plan sheet 14, these signs are located at the crosswalk just east of Gray Street near Station 6+75.

7. Are there details for these Pedestrian LED Signs?

The details of the installation are included in City Special Provision Section 614.

8. Regarding Schedule 3 – Removal of Fence (Split Rail) does not have quantity, is this correct?

The Denver Water side of 29th Ave doesn't have split rail.

The Schedule 4: Edgewater side of 29th Ave starting at Kendall, does require removal of 400 linear feet of split rail fence. See REVISED Bid Schedule 4, attached.

9. Regarding Schedule 4 – CDOT Curb Ramp Type 3B also has a zero quantity, is this correct?

This is correct. There is no CDOT Curb Ramp Type 3B.

9. Do please confirm the number of working days as 210 Working Days as on the Notice to Proceed it says 180 Working Days

Contract time is 210 working days. See REVISED Notice to Proceed, attached.

10. What are the liquidated damages?

Liquidated damages are in accordance with CDOT Standard Specifications Sub-section 108.09.

Visit our City website for prebid sign in sheet, addendum, plan holders list and project updates:
www.ci.wheatridge.co.us

POINT OF CONTACT: Jennifer Nellis, Purchasing Agent, jnellis@ci.wheatridge.co.us, fax 303-234-5924, or phone 303-235-2811. Do not contact the user department, consultant, or any other staff.

COMPANY SUBMITTING BID _____

BID Schedule #4 –W 29th Avenue – Edgewater

ITEM NO.	PAY ITEM	ESTIMATED QUANTITY	UNIT	UNIT PRICE	EXTENSION
201A	Clearing & Grubbing	1	LS	\$ _____	\$ _____
202A	Removal of Structures & Obstructions	1	LS	\$ _____	\$ _____
202B	Removal of Asphalt Mat (Planing)	271	SY	\$ _____	\$ _____
202C	Removal of Asphalt Mat (Full Depth)	1,725	SY	\$ _____	\$ _____
202D	Removal of Concrete Pavement	127	SY	\$ _____	\$ _____
202E	Removal of Fence (Split Rail)	400	LF	\$ _____	\$ _____
202F	Removal of Fence (Wire)	99	LF	\$ _____	\$ _____
202G	Removal of Landscape Areas	18	SY	\$ _____	\$ _____
202H	Removal of Tree (<12")	10	EA	\$ _____	\$ _____
202I	Removal of Tree (>12")	1	EA	\$ _____	\$ _____
202J	Removal of Inlet (Valley)	1	EA	\$ _____	\$ _____
203A	Unclassified Excavation	50	CY	\$ _____	\$ _____
203B	Embankment Material	1,250	CY	\$ _____	\$ _____
203C	Earthwork – Rough Grade	715	SY	\$ _____	\$ _____
203D	Earthwork – Fine Grade	715	SY	\$ _____	\$ _____
203E	Potholing	12	EA	\$ _____	\$ _____
208A	Erosion Control	1	LS	\$ _____	\$ _____
208B	Storm Drain Inlet Protection	1	EA	\$ _____	\$ _____
210A	Reset Fire Hydrant	1	EA	\$ _____	\$ _____
210B	Adjust Valve	2	EA	\$ _____	\$ _____
210C	Adjust Manhole Rim	1	EA	\$ _____	\$ _____
210D	Reset Mailbox (Type 1)	2	EA	\$ _____	\$ _____
210E	Reset Traffic Sign	3	EA	\$ _____	\$ _____
211A	Landscape Restoration	1	LS	\$ _____	\$ _____
212A	Seeding (Native)	636	SY	\$ _____	\$ _____
214A	Evergreen Tree	10	EA	\$ _____	\$ _____
SUBTOTAL THIS PAGE				\$ _____	

COMPANY SUBMITTING BID _____

ITEM NO.	PAY ITEM	ESTIMATED QUANTITY	UNIT	UNIT PRICE	EXTENSION
216A	Soil Retention Blanket	636	SY	\$ _____	\$ _____
304A	Aggregate Base Course (Class 6)(6")	200	TON	\$ _____	\$ _____
304B	Gravel Driveway	3	TON	\$ _____	\$ _____
306A	Reconditioning & Proofrolling	2,037	SY	\$ _____	\$ _____
403A	Hot Mix Asphalt (Grading SX)(2")	166	TON	\$ _____	\$ _____
403B	Hot Mix Asphalt (Grading S)(7")	578	TON	\$ _____	\$ _____
403C	Hot Mix Asphalt (2")	271	SY	\$ _____	\$ _____
412A	Concrete Pavement (6")	1,625	SY	\$ _____	\$ _____
604A	Valley Inlet, WR (Single)	1	EA	\$ _____	\$ _____
604B	Connect to existing pipe (18" PVC)	1	EA	\$ _____	\$ _____
608A	CDOT Curb Ramp Type 3B	0	EA	\$ _____	\$ _____
609A	Vertical Curb	61	LF	\$ _____	\$ _____
609B	Vertical Curb & Gutter	1,234	LF	\$ _____	\$ _____
609C	Pattern Concrete (4")	33	SY	\$ _____	\$ _____
614A	Steel Sign Post	24	LF	\$ _____	\$ _____
614B	Traffic Sign	2	EA	\$ _____	\$ _____
625A	Construction Surveying	1	LS	\$ _____	\$ _____
627A	Epoxy paint (4")(White) parking lot	880	LF	\$ _____	\$ _____
630A	Traffic Control Management	1	LS	\$ _____	\$ _____
720A	Materials Sampling & Testing	1	LS	\$ _____	\$ _____
SUBTOTAL THIS PAGE				\$ _____	
TOTAL AMOUNT OF BID SCHEDULE #4 \$				_____	
WRITTEN OUT AMOUNT OF BID SCHEDULE #4				_____	

NOTICE TO PROCEED

TO: _____

FROM: **CITY OF WHEAT RIDGE, CO**

RE: **ITB-18-26 – REBID, W 29TH AVE REALIGNMENT, PROJECT # S-01-16**

You are hereby notified to commence Work in accordance with the Agreement dated _____, 2019, on or before _____, 2019, and you are to complete the work within 180-210 working days. The date of completion of all work is _____, 2019

Dated this _____ day of _____ 2019

By: _____
Title: **Engineering Manager**

RECEIPT OF NOTICE

Receipt of the above Notice to Proceed is hereby acknowledged by

_____ on this _____ of _____, 2019

Printed Name _____

Signature _____

Title _____